



## DETAILS

REVISION				
REV.	ECO	DESCRIPTION	INIT	DATE
A		ENGINEERING RELEASE	SPJ	02/22/2017











NOTES:

- 1) CONCRETE: F<sub>C</sub> = 3000 PSI @ 28 DAYS.
- 2) REINFORCING STEEL: DEFORMED BARS ASTM A615 GRADE 60.
- 3) STATE AND LOCAL AGENCIES MAY HAVE VARIOUS REQUIREMENTS FOR APPROACH RAMP LENGTH, PITCH, AND FOR CLEAN OUT HEIGHT. PLEASE CHECK WITH ALL AGENCIES PRIOR TO CONSTRUCTION.
- 4) MONOLITHIC POUR IS ALLOWED AT CONTRACTOR'S DISCRETION.
- 5) DEVELOP AND MAINTAIN SITE GRADES WHICH WILL RAPIDLY DRAIN SURFACE AND ROOF RUN-OFF AWAY FROM FOUNDATION.
- 6) FOOTINGS HAVE BEEN DESIGNED FOR A MINIMUM SOIL PRESSURE OF 2500 PSF. IT WILL BE THE RESPONSIBILITY OF OTHERS TO VERIFY THIS VALUE.
- 7) WHERE REINFORCING BARS ARE SHOWN CONTINUOUS, LAP SPLICE BARS 40 DIAMETERS
- 8) APPROACHES TO BE A COMMON PLANE WITHIN 1/4".

⑨ APPROACH THICKNESS MAY BE 10" MINIMUM WHERE ALLOWED BY STATE REGULATIONS


⑩ FOUNDATION MUST EXTEND A MINIMUM OF 12" BELOW THE FROST PENETRATION LINE

(REVISOR) RT DATE <b>S. JOHNSON</b> <b>02/22/2017</b>		DRAWN BY DATE <b>S. JOHNSON</b> <b>02/22/2017</b>		FIELD PROPOSAL DATE <b>S. JOHNSON</b> <b>02/27/2017</b>			
(TREATMENT) <b>NONE</b>		THIS DRAWING AND INFORMATION CONTAINED HEREIN IS AND REMAINS THE PROPERTY OF RICE LAKE WEIGHING SYSTEMS, INC. HEREINAFTER REFERRED TO AS "RICE LAKE". IT IS TO BE USED ONLY FOR THE PURPOSES, PROPOSAL AND/OR USE ITS CUSTOMER'S COMPANY. IT SHALL NOT BE REPRODUCED OR COPIED WITHOUT RICE LAKE'S WRITTEN CONSENT AND SHALL BE IMMEDIATELY RETURNED UPON REQUEST.		UNLESS OTHERWISE SPECIFIED UNITS SHALL BE INCHES. ALL THREADS TO BE CLASS 2 ALL DIMENSIONS APPLICABLE AFTER TREATMENT			
(NUMBER OF CIRCLES) 		(TOLERANCE) DO NOT SCALE DRAWING TOLERANCES UNLESS OTHERWISE SPECIFIED .XX: ± .XXX: ± ✓ ANGLE: ±		(DESCRIPTION) <b>FOUNDATION, CONCRETE PIER 70' X 12' OTR SERIES TRUCK SCALE</b>			
(MINIMUM CRANE CAPACITY) 		(SCALE) 1:45		(SHEET) 1 OF 3		(MATERIAL) 	
(ESTIMATED WEIGHT POUNDS) 		(THIRD ANGLE PROJECTION) 		(PIV) <b>180298</b>		(REV) <b>A</b>	


CONCRETE SCHEDULE			
		VOLUME (CUBIC YARDS)	
APPROACHES		10.1	
CLEANOUT		9.0	
PIERS		13.7	
TOTAL		32.8	
MISC. STEEL			
PIT COPING	3 X 3 X 1/4	23 LN .FT	113 LBS

VOLUME SHOWN FOR STATED PIER DEPTH.  
ADD ADDITIONAL CONCRETE FOR  
DEEPER PIERS AS NEEDED.




## CONCRETE LAYOUT





DETAIL C




DETAIL D




DESIGNED BY DATE S. JOHNSON 02/22/2017		DRAWN BY DATE S. JOHNSON 02/22/2017		PIER APPROVAL DATE S. JOHNSON 03/27/2017		<div><div></div><div><b>RICE LAKE</b></div><div><b>WEIGHING SYSTEMS</b></div></div>			
TREATMENT  NONE		THIS DRAWING AND INFORMATION CONTAINED HEREIN IS AND REMAINS THE PROPERTY OF RICE LAKE WEIGHING SYSTEMS INC. - HEREINAFTER REFERRED TO AS RLWS. IT MAY BE USED ONLY FOR RLWS' PROPOSAL AND/OR ITS CUSTOMER'S ORDERS. IT SHALL NOT BE DISCLOSED OR COPIED WITHOUT RLWS SPECIFIC WRITTEN CONSENT AND SHALL BE IMMEDIATELY RETURNED UPON REQUEST.		UNLESS OTHERWISE SPECIFIED UNITS TO BE INCHES ALL THREADS TO BE CLASS 2 ALL DIMENSIONS APPLICABLE AFTER TREATMENT					
NUMBER OF CRANES:  MINIMUM CRANE CAPACITY:  ESTIMATED WEIGHT (POUNDS):		<div><div></div><div>DO NOT SCALE DRAWING SURFACE FINISH ✓ ANGLE:</div></div>		TOLERANCES DRAWINGS TOLERANCES UNLESS OTHERWISE SPECIFIED XX: XXX: ✓ ANGLE:		DESCRIPTION FOUNDATION, CONCRETE PIER 70" X 12" OTR SERIES TRUCK SCALE			
				SCALE 1:45	SHEET 2 OF 3	MATERIAL	THIRD ANGLE PROJECTION 	PIY 180298	REV A

MATERIAL REQUIREMENTS				
REBAR SCHEDULE				
BAL. NO.	QUANTITY	LENGTH (FT-IN.)	DESCRIPTION	WEIGHT
A	26	9' 6"	# 4 @ 12 O.C.	165
B	26	11' 10"	# 4 @ 12 O.C.	206
C	26	1' 9 3/4"	# 4 @ 12 O.C.	31
D	26	4' 0"	# 4 @ 12 O.C.	69
E	26	11' 10"	# 4 @ 4 O.C.	206
F	26	2' 6"	# 4 @ 12 O.C.	43
G	18	11' 10"	# 4 @ 4 O.C.	142
CLEANOUT SCHEDULE				
H	6	17' 10 1/2"	# 4 @ 24 O.C.	72
J	6	19' 10"	# 4 @ 24 O.C.	79
K	6	19' 9"	# 4 @ 24 O.C.	79
L	29	11' 10"	# 4 @ 24 O.C.	229
TOTAL WEIGHT OF REBAR (LBS.)				1322
TOTAL LENGTH OF REBAR (FT.)				1979




## APPROACH STANDARD VIEWS


**NOTES:** 1) LEFT AND RIGHT APPROACHES ARE MIRROR IMAGES OF EACH OTHER AND CONTAIN AN IDENTICAL PART LIST






## APPROACH PIER STANDARD VIEWS



## PIER STANDARD VIEWS



DESIGNED BY DATE S. JOHNSON 02/22/2017		DRAWN BY DATE S. JOHNSON 02/22/2017		FIELD ERECTING DATE S. JOHNSON 03/27/2017			
TREATMENT  NONE		THIS DRAWING AND INFORMATION CONTAINED HEREIN IS AND REMAINS THE PROPERTY OF RICE LAKE WEIGHING SYSTEMS INC. HEREINAFTER REFERRED TO AS RLS. IT MAY BE USED FOR THE RLS' PROPOSAL AND/OR ITS CUSTOMER'S PROJECT. IT SHALL NOT BE REPRODUCED OR COPIED WITHOUT RLS'S SPECIFIC WRITTEN CONSENT AND SHALL BE IMMEDIATELY RETURNED UPON REQUEST.		UNLESS OTHERWISE SPECIFIED UNITS TO BE IN INCHES ALL THREADS TO BE CLASS 2 ALL DIMENSIONS APPLICABLE AFTER TREATMENT			
NUMBER OF CRANES  MINIMUM CRANE CAPACITY  (ESTIMATED WEIGHT POINTS)		 DO NOT SCALE DRAWING SURFACE FINISH  <input checked="" type="checkbox"/> ANGLE: ±		DESCRIPTION  FOUNDATION, CONCRETE PIER 70' x 12' OTR SERIES TRUCK SCALE		SCALE  1:48	
		TOLERANCES UNLESS OTHERWISE SPECIFIED .XX; ± .XXX; ± <input checked="" type="checkbox"/> ANGLE: ±		SHEET  3 OF 3		MATERIAL  180298	
				BIRD ANGLE PROJECTION 		REV  A	